

Bundle, Mark, Protect and Load



1. Bundle

Steel straps, frames or skids selected for panel mass and handling method.

2. Mark

Bundle tags aligned to packing list, panel schedule and drawing marks.

3. Protect

Finished surfaces, corners and exposed edges protected for transit.

4. Load

Container sequence planned around weight distribution, unloading and site access.

